


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☒**APPLICATION FOR PERMIT TO DRILL**

<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				<b>1. WELL NAME and NUMBER</b> NBU 920-12F		
<b>4. TYPE OF WELL</b> Gas Well Coalbed Methane Well: NO				<b>3. FIELD OR WILDCAT</b> NATURAL BUTTES		
<b>6. NAME OF OPERATOR</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.				<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> NATURAL BUTTES		
<b>8. ADDRESS OF OPERATOR</b> P.O. Box 173779, Denver, CO, 80217				<b>7. OPERATOR PHONE</b> 720 929-6587		
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> UTU-0144868-B		<b>11. MINERAL OWNERSHIP</b> FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		<b>9. OPERATOR E-MAIL</b> mary.mondragon@anadarko.com		
<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>		
<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>				<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>		
<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>		<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b> Ute Indian Tribe		<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		
<b>19. SLANT</b> VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>		<b>20. LOCATION OF WELL</b>				
<b>LOCATION AT SURFACE</b>		<b>FOOTAGES</b>		<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>
<b>Top of Uppermost Producing Zone</b>		1957 FNL 1922 FWL		SE NW	12	9.0 S
<b>At Total Depth</b>		1957 FNL 1922 FWL		SE NW	12	9.0 S
<b>21. COUNTY</b> UINTAH		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 1922		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 600		
<b>24. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 1500		<b>25. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 1922		<b>26. PROPOSED DEPTH</b> MD: 10800 TVD: 0		
<b>27. ELEVATION - GROUND LEVEL</b> 4704		<b>28. BOND NUMBER</b> WYB-000291		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> Permit #43-8496		

**ATTACHMENTS****VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**


<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP
<b>NAME</b> Raleen White	<b>TITLE</b> Sr. Regulatory Analyst
<b>SIGNATURE</b>	<b>PHONE</b> 720 929-6666
<b>API NUMBER ASSIGNED</b> 43047501810000	<b>DATE</b> 12/30/2008
<b>APPROVAL</b>	<b>EMAIL</b> raleen.white@anadarko.com
 Permit Manager	

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2800		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	2800	36.0			
	Cement Interval	Top (MD)	Bottom (MD)			
		0	2800			
		Cement Description	Class	Sacks	Yield	Weight
			Premium Foamed Cement	315	1.18	15.6




Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	10800		
Pipe	Grade	Length	Weight			
	Grade I-80 LT&C	10800	11.6			
	Cement Interval	Top (MD)	Bottom (MD)			
		0	10800			
		Cement Description	Class	Sacks	Yield	Weight
			Premium Lite High Strength	520	3.38	12.5
			Possolan-Lime Cement	1680	1.31	14.3

# T9S, R20E, S.L.B.&M.



## NOTES:

- ▲ = Section Corners Located
- 1. Well footages are measured at right angles to the Section Lines.
- 2. G.L.O. distances are shown in feet or chains. 1 chain = 66 feet.
- 3. Bearings are based on Global Positioning Satellite observations.
- 4. Basis of elevation is the Northwest Corner of Section 12, T9S, R20E, S.L.B.&M. The elevation of this Section Corner is shown on the Qaray SE 7.5 Min. Quadrangle as being 4676'.



## SURVEYOR'S CERTIFICATE


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

John R. Maugh  
REGISTERED LAND SURVEYOR  
REGISTRATION No. 6028691  
STATE OF UTAH

**Kerr-McGee  
Oil & Gas Onshore, LP**

1099 18th Street - Denver, Colorado 80202

**NBU 920-12F  
WELL PLAT**  
1957' FNL, 1922' FWL  
SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  OF SECTION 12, T9S, R20E,  
S.L.B.&M. UTAH COUNTY, UTAH.



CONSULTING, LLC  
371 Coffeen Avenue  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

**TIMBERLINE**


ENGINEERING & LAND SURVEYING, INC.

38 WEST 100 NORTH - VERNAL, UTAH 84078

DATE SURVEYED: 06-23-08	SURVEYED BY: M.S.B.	SHEET <b>1</b> OF 9
DATE DRAWN: 07-07-08	DRAWN BY: B.R.B.	
SCALE: 1" = 1000'	Date Last Revised:	

(435) 789-1365

'APIWellNo:43047501810000'



#### WELL PAD LEGEND

- WELL LOCATION
- EXISTING CONTOURS (1' INTERVAL)
- PROPOSED CONTOURS (1' INTERVAL)

#### WELL PAD NBU 920-12F QUANTITIES

EXISTING GRADE @ LOC. STAKE = 4,688.9'

FINISHED GRADE ELEVATION = 4,688.2'

CUT SLOPES = 1.5:1

FILL SLOPES = 1.5:1

TOTAL CUT FOR WELL PAD = 2,023 C.Y.

TOTAL FILL FOR WELL PAD = 1,900 C.Y.

TOPSOIL @ 6" DEPTH = 2,879 C.Y.

TOTAL DISTURBANCE = 3.57 ACRES

SHRINKAGE FACTOR = 1.15

SWELL FACTOR = 1.00

RESERVE PIT CAPACITY (2' OF FREEBOARD)

+/- 25,880 BARRELS

RESERVE PIT VOLUME


+/- 7,185 CY

BACKFLOW PIT CAPACITY (2' OF FREEBOARD)

+/- 8,780 BARRELS

BACKFLOW PIT VOLUME

+/- 2,520 CY



HORIZONTAL 0 50 100 1" = 100'  
1' CONTOURS

#### KERR-MCGEE OIL & GAS ONSHORE L.P.

1099 18th Street - Denver, Colorado 80202



CONSULTING, LLC  
371 Coffeen Avenue  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

Scale: 1"=100' Date: 8/15/08

SHEET NO:

REVISED:


BY  
DATE

2


2 OF 9

NBU 920-12F  
WELL PAD - LOCATION LAYOUT  
1957' FNL, 1922' FWL  
SE1/4NW1/4, SECTION 12, T.9S., R.20E.  
S.L.B.&M., UINTAH COUNTY, UTAH

**Timberline** (435) 789-1365  
Engineering & Land Surveying, Inc.  
38 WEST 100 NORTH VERNAL, UTAH 84078



**CROSS SECTION A-A'**



**CROSS SECTION B-B'**

**KERR-MCGEE OIL & GAS  
ONSHORE L.P.**

1099 18th Street - Denver, Colorado 80202

**NBU 920-12F  
WELL PAD - CROSS SECTIONS  
1957' FNL, 1922' FWL  
SE1/4NW1/4, SECTION 12, T.9S., R.20E.  
S.L.B.&M., UTAH COUNTY, UTAH**



**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

Scale: 1"=100' Date: 8/15/08

REVISED:

BY  
DATE

SHEET NO:

**3**

3 OF 9



HORIZONTAL 0 50 100 1" = 100'  
VERTICAL 0 10 20 1" = 20'

**Timberline** (435) 789-1365  
*Engineering & Land Surveying, Inc.*  
38 WEST 100 NORTH VERNAL, UTAH 84078






PHOTO VIEW: TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHEASTERLY

**Kerr-McGee**  
**Oil & Gas Onshore, LP**  
 1099 18th Street — Denver, Colorado 80202

NBU 920-12F  
 1957' FNL, 1922' FWL  
 SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  OF SECTION 12, T9S, R20E,  
 S.L.B.&M. UTAH COUNTY, UTAH.



CONSULTING, LLC  
 371 Coffeen Avenue  
 Sheridan WY 82801  
 Phone 307-674-0609  
 Fax 307-674-0182

**LOCATION PHOTOS**

DATE TAKEN: 07-29-08

DATE DRAWN: 07-31-08

TAKEN BY: JD.H

DRAWN BY: B.R.B.

REVISED:

**Timberline**


(435) 789-1365

Engineering &amp; Land Surveying, Inc.

38 WEST 100 NORTH VERNAL, UTAH 84078

**SHEET**  
**4**  
**OF 9**





### Legend

- Proposed NBU 920-12F Well Location
- Access Route - Proposed

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street, Denver, Colorado 80202

**NBU 920-12F**  
**Topo A**  
**1957' FNL, 1922' FWL**  
**SE¼ NW¼, Section 12, T9S, R20E**  
**S.L.B.&M., Uintah County, Utah**

  
**609**  
**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182




Scale: 1:100,000	NAD83 USP Central
Drawn: JELO	Date: 14 Aug 2008
Revised:	Date:

Sheet No:

**5**

5 of 9





### Legend

- Well - Proposed
- Well Pad
- - - Road - Proposed
- Road - Existing

Total Proposed Road Length = ±375 ft

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street, Denver, Colorado 80202

**NBU 920-12F**  
**Topo B**  
**1957' FNL, 1922' FWL**  
**SE¼ NW¼, Section 12, T9S, R20E**  
**S.L.B.&M., Uintah County, Utah**

**609**  
**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182



Scale: 1" = 2000ft  
NAD83 USP Central  
Drawn: JELO  
Revised:


Date: 14 Aug 2008  
Date:

Sheet No:

**6**

6 of 9





### Legend

- Well - Proposed
- Well - 1 Mile Radius
- Producing
- ▲ Approved permit (APD); not yet spudded
- Spudded (Drilling commenced: Not yet comple
- ✕ Location Abandoned
- Shut-In
- Well Pad
- Temporarily-Abandoned
- ✕ Plugged and Abandoned

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street, Denver, Colorado 80202

**NBU 920-12F**  
**Topo C**  
**1957' FNL, 1922' FWL**  
**SE¼ NW¼, Section 12, T9S, R20E**  
**S.L.B.&M., Uintah County, Utah**


**609**  
**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182



Scale: 1" = 2000ft | NAD83 USP Central  
Drawn: JELO | Date: 14 Aug 2008  
Revised: | Date:

Sheet No:  
**7**  
7 of 9





### Legend

- Well - Proposed
- Well Pad
- - - Pipeline - Proposed
- - - Road - Proposed
- Pipeline - Existing
- Road - Existing

Total Proposed Pipeline Length: ±603ft

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street, Denver, Colorado 80202

**NBU 920-12F**

**Topo D**

**1957' FNL, 1922' FWL**

**SE¼ NW¼, Section 12, T9S, R20E**

**S.L.B.&M., Uintah County, Utah**



**609 CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182



Scale: 1" = 2000ft  
NAD83 USP Central  
Drawn: JELO  
Revised:

Date: 14 Aug 2008  
Date:

Sheet No:

**8**

8 of 9



**Kerr-McGee Oil & Gas Onshore, LP**  
**NBU 920-12F**  
**Section 12, T9S, R20E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 13.9 MILES TO THE JUNCTION OF STATE HIGHWAY 88. EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 88 APPROXIMATELY 16.8 MILES TO OURAY, UTAH. FROM OURAY, PROCEED IN A SOUTHERLY DIRECTION ALONG THE SEEP RIDGE ROAD (COUNTY B ROAD 2810) APPROXIMATELY 2.9 MILES TO THE INTERSECTION OF AN EXISTING ROAD TO THE EAST. EXIT LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION ALONG EXISTING ROAD APPROXIMATELY 3.8 MILES TO THE INTERSECTION OF AN EXISTING ROAD TO THE SOUTH. EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG EXISTING ROAD APPROXIMATELY 0.5 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 375 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 38.0 MILES IN A SOUTHERLY DIRECTION.

**NBU 920-12F  
SENW Sec. 12, T9S, R20E  
UINTAH COUNTY, UTAH  
UTU-0144868-B**

**ONSHORE ORDER NO. 1**

***DRILLING PROGRAM***

**1. Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1822'
Bird's Nest	2086'
Mahogany	2616'
Wasatch	5284'
Mesaverde	8530'
MVU2	9521'
MVL1	10029'
TD	10800'

**2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1822'
	Bird's Nest	2086'
	Mahogany	2616'
Gas	Wasatch	5284'
Gas	Mesaverde	8530'
Gas	MVU2	9521'
Gas	MVL1	10029'
Water	N/A	
Other Minerals	N/A	

**3. Pressure Control Equipment (Schematic Attached)**

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

**4. Proposed Casing & Cementing Program:**

*Please see the Natural Buttes Unit SOP.*

**5. Drilling Fluids Program:**

*Please see the Natural Buttes Unit SOP.*

**6. Evaluation Program:**

*Please see the Natural Buttes Unit SOP.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 10800' TD, approximately equals 6696 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 4320 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

9. **Variances:**

*Please see Natural Buttes Unit SOP Onshore Order #2 – Air Drilling Variance  
Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several  
requirements associated with air drilling outlined in Onshore Order 2*

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

*This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.*

*The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.*

*More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.*

*Background*

*In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet.*

*The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.*

*Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.*

*The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole*

*to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.*

*KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.*

#### *Variance for BOPE Requirements*

*The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.*

#### *Variance for Mud Material Requirements*

*Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.*

#### *Variance for Special Drilling Operation (surface equipment placement) Requirements*

*Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.*

*Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.*

*Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.*

*Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.*

*Conclusion*

*The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above..*


**10. Other Information:**

*Please see Natural Buttes Unit SOP.*



# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP	DATE	September 11, 2008	
WELL NAME	NBU 920-12F	TD	10,800' MD/TVD	
FIELD	Natural Buttes	COUNTY	Uintah	STATE
			Utah	
SURFACE LOCATION	SENW - 1957' FNL, 1922' FWL, SECTION 12, T9S, R20E		ELEVATION	4,889' GL KB 4,704'
	Latitude: 40.051980 Longitude: -109.617140		NAD 27	
OBJECTIVE ZONE(S)	Mesaverde			
ADDITIONAL INFO	Regulatory Agencies: BLM (MINERALS), BIA (SURFACE), UDOGM, Tri-County Health Dept.			





# **KERR-McGEE OIL & GAS ONSHORE LP** **DRILLING PROGRAM**

## **CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3520	2020	453000
SURFACE	9-5/8"	0 to 2,800'	38.00	J-55	LTC	0.76	1.54	5.13
						7750	8360	201000
PRODUCTION	4-1/2"	0 to 10800	11.60	I-80	LTC	1.68	0.90	1.84

1) Max Anticipated Surf. Press. (MASP) (Surface Casing) = (Pore Pressure at next csg point - (0.22 psi/ft - partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft - partial evac gradient x TD)

(Burst Assumptions: TD = 12.5 ppg)

.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing \* Buoy. Fact. of water)

MASP 4320 psi

## **CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 25 pps floccle				
	TOP OUT CMT (1)	250	20 gals sodium silicate + Premium cmt	100		15.60	1.18
			+ 2% CaCl + 25 pps floccle				
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2			NOTE: If well will circulate water to surface, option 2 will be utilized.				
	LEAD	2000	Prem cmt + 16% Gel + 10 pps gilsonite	230	35%	11.00	3.82
			+ 25 pps Floccle + 8% split BWOC				
	TAIL	500	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 25 pps floccle				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,780'	Premium Lite II + 3% KCl + 0.25 pps cellofacke + 5 pps gilsonite + 10% gel + 0.5% extender	520	60%	12.50	3.38
	TAIL	6,020'	50/50 Poz/G + 10% salt + 2% gel + 1% R-3	1680	60%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

## **ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 6M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder &

four sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper

& lower kelly valves.

Drop Tolco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

NBU 920-12F



**NBU 920-12F  
SENW SEC. 12 ,T9S,R20E  
UINTAH COUNTY, UTAH  
UTU-0144868-B**

**ONSHORE ORDER NO. 1**

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

**1. Existing Roads:**

Refer to the attached location directions.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

**2. Planned Access Roads:**

No new access road is planned, as this is a twin location. Refer to Topo Map B.

*Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.*

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*Please see the Natural Buttes Unit SOP.*

Refer to Topo Map D for the location of the proposed pipelines.

**Variances to Best Management Practices (BMPs) Requested:**

This exception to the BMP should be granted by the BLM Authorized Officer because indurated bedrock, such as sandstone, is at or within 2 feet of the surface and the soil has a poor history for successful rehabilitation.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Shadow gray, a non-reflective earthtone.

**Interim Surface Reclamation Plan:**

This exception is requested due to the current twin and multi-well program. If determined that this well will not be a candidate for either twinning &/or multi-well the operator shall spread the topsoil pile on the location up to the rig anchor points. The location will be reshaped to the

original contour to the extent possible. The operator will reseed the area using the BLM recommended seed mixture and reclamation methods.

**5. Location and Type of Water Supply:**

*Please see the Natural Buttes SOP.*

**6. Source of Construction Materials:**

*Please see the Natural Buttes SOP.*

**7. Methods of Handling Waste Materials:**

*Please see the Natural Buttes SOP.*

A plastic reinforced liner is to be used as discussed during on-site inspection. It will be a minimum of 20 mil thick and felt, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E, Pipeline Facility Sec. 36, T9S, R20E, Goat Pasture Evaporation Pond SW/4 Sec. 16, T10S, R22E, Bonanza Evaporation Pond Sec. 2, T10S, R23E (*Request is in lieu of filing Form 3160-5, after initial production*).

**8. Ancillary Facilities:**

*Please see the Natural Buttes SOP.*

**9. Well Site Layout: (See Location Layout Diagram)**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

Location size may change prior to the drilling of the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling rig. The location will be re-surveyed and a form 3160-5 will be submitted.

**10. Plans for Reclamation of the Surface:**

*Please see the Natural Buttes SOP.*

Operator shall call the BIA for the seed mixture when final reclamation occurs.

**11. Surface/Mineral Ownership:**

The well pad and access road are located on lands owned by:

Ute Indian Tribe  
P.O. Box 70  
Fort Duchesne, Utah 84026  
(435) 722-5141

The mineral ownership is listed below:

United States of America  
Bureau of Land Management  
170 South 500 East  
Vernal, UT 84078  
(435) 781-4400

**12. Stipulations/Notices/Mitigation:**

There are no stipulations or notices for this location.

**13. Other Information:**

A Class III archaeological survey has been performed and will be submitted. Attached is the cover page for the Paleontological Report (IPC 08-142).

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within the boundaries of the Unit.

**14. Lessee's or Operator's Representative & Certification:**

Raleen White  
Sr. Regulatory Analyst  
Kerr-McGee Oil & Gas Onshore LP  
P.O. Box 173779  
Denver, CO 80217-3779  
(720) 929-6666

Randy Bayne  
Drilling Manager  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East  
Vernal, UT 84078  
(435) 781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under the terms and conditions of the lease for the operations conducted upon leased lands.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.



Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Indian Affairs Nationwide Bond #RLB0005239.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

  
Raleen White

9/11/2008  
Date

# EXHIBIT A



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

**Kerr-McGee Oil & Gas Onshore, LP**  
**NBU 920-12F**  
**Section 12, T9S, R20E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 13.9 MILES TO THE JUNCTION OF STATE HIGHWAY 88. EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 88 APPROXIMATELY 16.8 MILES TO OURAY, UTAH. FROM OURAY, PROCEED IN A SOUTHERLY DIRECTION ALONG THE SEEP RIDGE ROAD (COUNTY B ROAD 2810) APPROXIMATELY 2.9 MILES TO THE INTERSECTION OF AN EXISTING ROAD TO THE EAST. EXIT LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION ALONG EXISTING ROAD APPROXIMATELY 3.8 MILES TO THE INTERSECTION OF AN EXISTING ROAD TO THE SOUTH. EXIT RIGHT AND PROCEED IN A SOUTHERLY DIRECTION ALONG EXISTING ROAD APPROXIMATELY 0.5 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 375 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 38.0 MILES IN A SOUTHERLY DIRECTION.

S89°20'W 79.02 (G.L.O.)  
(Meas.) S89°21'

S89°21'44"W - 2608.33' (Meas.)

S89°19'55"W - 2606.52' (Meas.)

Found 1968  
Brass Cap.  
Pile of Stones.

N0015'42"W - 2665.17' (Meas.)  
N017"W 40.38 (G.L.O.)

..L.O.)  
N00°23'35"E - 2659.69' (Meas.)

N00°21'43"E — 2659.80' (Meas.)

Found 1968  
Brass Cap.  
Pile of Stones.

Proposed  
Well

12

**WELL LOCATION:**  
**NBU 920-12F**

ELEV. UNGRADED GROUND = 4688.9'

NBU 920-12F (Proposed Well Head)

NAD 83 LATITUDE = 40.05193° (40° 03' 06.93")  
LONGITUDE = 109.61783° (109° 37' 04.19")

NAD 27 LATITUDE = 40.05196° (40° 03' 07.06")  
LONGITUDE = 109.61714° (109° 37' 01.70")

Found 1968  
Brass Cap.  
Pile of Stones.

Found 1968  
Brass Cap.  
Pile of Stones.

Found 1968  
Brass Cap.  
Pile of Stones.

S88°55'40"W (Basis of Bearings)  
2670.83' (Measured)  
S88°53'W 40.48 (G.L.O.)

S88°55'55"W - 2612.51' (Meas.)  
S88°55'W 39.58 (G.L.O.)

 = Section Corners Located

1. Well footages are measured at right angles to the Section Lines.
2. G.L.O. distances are shown in feet or chains. 1 chain = 66 feet.
3. Bearings are based on Global Positioning Satellite observations.
4. Basis of elevation is the Northwest Corner of Section 12, T9S, R20E, S.L.B.&M. The elevation of this Section Corner is shown on the Ouray SE 7.5 Min. Quadrangle as being 4676'.

SCALE

## SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF AGRICULTURAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION, AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. No. 6028691

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 60286  
STATE OF UTAH

Kerr-McGee  
Oil & Gas Onshore, LP

1099 18th Street - Denver, Colorado 80202

NBU 920-12F  
WELL PLAT

1957' FNL, 1922' FWL

SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  OF SECTION 12, T9S, R20E,  
S.L.B.&M. UTAH COUNTY, UTAH.

**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

## TIMBERLINE

(435) 789-1365

**ENGINEERING & LAND SURVEYING, INC.**

38 WEST 100 NORTH - VERNAL, UTAH 84078

DATE SURVEYED:  
06-23-08

SURVEYED BY: M.S.B.

**SHEET**

DATE DRAWN:  
07-07-08

DRAWN BY: B.R.B.

1

SCALE: 1" = 1000'

Date Last Revised:

OF 9

# WELL PAD LEGEND

- WELL LOCATION
- EXISTING CONTOURS (1' INTERVAL)
- PROPOSED CONTOURS (1' INTERVAL)

## WELL PAD NBU 920-12F QUANTITIES



EXISTING GRADE @ LOC. STAKE = 4,688.9'  
FINISHED GRADE ELEVATION = 4,688.2'  
CUT SLOPES = 1.5:1  
FILL SLOPES = 1.5:1

TOTAL CUT FOR WELL PAD = 2,023 C.Y.  
TOTAL FILL FOR WELL PAD = 1,900 C.Y.  
TOPSOIL @ 6" DEPTH = 2,879 C.Y.  
TOTAL DISTURBANCE = 3.57 ACRES  
SHRINKAGE FACTOR = 1.15  
SWELL FACTOR = 1.00  
RESERVE PIT CAPACITY (2' OF FREEBOARD)  
+/- 25,880 BARRELS  
RESERVE PIT VOLUME  
+/- 7,185 C.Y.  
BACKFLOW PIT CAPACITY (2' OF FREEBOARD)  
+/- 8,780 BARRELS  
BACKFLOW PIT VOLUME  
+/- 2,520 C.Y.



HORIZONTAL 0 50 100 1" = 100'  
1' CONTOURS

**Timberline**  
Engineering & Land Surveying, Inc.  
38 WEST 100 NORTH VERNAL, UTAH 84078  
(435) 789-1365




CONSULTING, LLC  
371 Coffeen Avenue  
Sheridan WY 82801  
Phone 307-674-0609  
Fax 307-674-0182

KERR-MCGEE OIL & GAS  
ONSHORE L.P.  
1099 18th Street - Denver, Colorado 80202


NBU 920-12F  
WELL PAD - LOCATION LAYOUT  
1957' FNL, 1922' FWL  
SE1/4NW1/4, SECTION 12, T.9S., R.20E.  
S.L.B.&M., UINTAH COUNTY, UTAH

Scale: 1"=100'  
Date: 8/15/08  
SHEET NO: 2  
2 OF 9  
REVISED: BY DATE






**CROSS SECTION A-A'**




**CROSS SECTION B-B'**



**KERR-MCGEE OIL & GAS**  
**ONSHORE L.P.**  
 1099 18th Street - Denver, Colorado 80202

**NBU 920-12F**  
**WELL PAD - CROSS SECTIONS**  
 1957' FNL, 1922' FWL  
 SE1/4NW1/4, SECTION 12, T.9S., R.20E.  
 S.L.B.&M., Uintah County, Utah



**609 CONSULTING, LLC**  
 371 Coffeen Avenue  
 Sheridan WY 82801  
 Phone 307-674-0609  
 Fax 307-674-0182

**Timberline** (435) 789-1365  
**Engineering & Land Surveying, Inc.**  
 38 WEST 100 NORTH  
 VERNAL, UTAH 84078

Scale: 1"=100'	Date: 8/15/08	SHEET NO: 3
REVISED:	BY	DATE
		3 OF 9




PHOTO VIEW: TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY




PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHEASTERLY

**Kerr-McGee**  
**Oil & Gas Onshore, LP**  
 1099 18th Street - Denver, Colorado 80202

NBU 920-12F  
 1957' FNL, 1922' FWL  
 SE  $\frac{1}{4}$  NW  $\frac{1}{4}$  OF SECTION 12, T9S, R20E,  
 S.L.B.&M. UTAH COUNTY, UTAH.




CONSULTING, LLC  
 371 Coffeen Avenue  
 Sheridan WY 82801  
 Phone 307-674-0609  
 Fax 307-674-0182

LOCATION PHOTOS		
TAKEN BY: J.D.H.	DRAWN BY: B.R.B.	DATE TAKEN: 07-29-08
		DATE DRAWN: 07-31-08
		REVISED:

<b>Timberline</b> Engineering & Land Surveying, Inc. 38 WEST 100 NORTH VERNAL, UTAH 84078	(435) 789-1365	SHEET 4 OF 9
---	----------------	--------------------



### Legend

- Proposed NBU 920-12F Well Location
- Access Route - Proposed

**Kerr-McGee Oil & Gas Onshore, LP**  
1099 18th Street, Denver, Colorado 80202

**NBU 920-12F**

**Topo A**

**1957' FNL, 1922' FWL**  
**SE¼ NW¼, Section 12, T9S, R20E**  
**S.L.B.&M., Uintah County, Utah**



**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182



Scale: 1:100,000

NAD83 USP Central

Sheet No:

Drawn: JELo

Date: 14 Aug 2008

Revised:

Date:

**5**

5 of 9

 Well - Proposed  
  Well Pad  
  Road - Proposed  
 Road - Existing

NBU 920-12F  
Topo B  
1957' FNL, 1922' FWL  
SE¼ NW¼, Section 12, T9S, R20E  
S.L.B.&M., Uintah County, Utah



**CONSULTING, LLC**  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182




Scale: 1" = 2000ft	NAD83 USP Central	Sheet No:
Drawn: JELO	Date: 14 Aug 2008	6
Revised:	Date:	

6

6 of 9



## 7 of 9



# Legend

- Well - Proposed
- Well Pad
- Pipeline - Proposed
- Road - Proposed
- Pipeline - Existing
- Road - Existing

Total Proposed Pipeline Length: ±603ft

Kerr-McGee Oil & Gas Onshore, LP  
1099 18th Street, Denver, Colorado 80202

NBU 920-12F

Topo D

1957' FNL, 1922' FWL

SE¼ NW¼, Section 12, T9S, R20E

S.L.B.&M., Uintah County, Utah



CONSULTING, LLC  
371 Coffeen Avenue  
Sheridan, WY 82801  
Phone (307) 674-0609  
Fax (307) 674-0182

Scale: 1" = 2000ft

NAD83 USP Central

Sheet No:

Drawn: JELo

Date: 14 Aug 2008

Revised:

Date:

8

8 of 9

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160  
(UT-922)

October 14, 2008

Memorandum

To: Assistant District Manager Minerals, Vernal District  
From: Michael Coulthard, Petroleum Engineer  
Subject: 2008 Plan of Development Natural Buttes Unit  
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2008 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ WASATCH-MESAVERDE)

43-047-50179	NBU 920-12H Sec 12 T09S R20E 2170 FNL 0279 FEL	
43-047-50180	NBU 920-12G Sec 12 T09S R20E 2151 FNL 2191 FEL	
43-047-50181	NBU 920-12F Sec 12 T09S R20E 1957 FNL 1922 FWL	
43-047-50185	NBU 920-29A Sec 29 T09S R20E 0616 FNL 0927 FEL	
43-047-50174	NBU 920-12B Sec 12 T09S R20E 0627 FNL 1964 FEL	
43-047-50186	NBU 920-29D Sec 29 T09S R20E 0552 FNL 0859 FWL	

(Proposed PZ MESAVERDE)

43-047-50162	NBU 920-12LT Sec 12 T09S R20E 1538 FSL 0792 FWL	
43-047-50161	NBU 920-24AT Sec 24 T09S R20E 0709 FNL 0704 FEL	

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:10-14-08



API Number: 4304750181

Well Name: NBU 920-12F

Township 09.0 S Range 20.0 E Section 12

Meridian: SLBM

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:  
Map Produced by Diana Mason

Units

STATUS

ACTIVE

EXPLORATORY

GAS STORAGE

NF PP OIL

NF SECONDARY

PI OIL

PP GAS

PP GEOTHERML

PP OIL

SECONDARY

TERMINATED

Fields

STATUS

ACTIVE

COMBINED

Sections

Township

Wells Query Events

<all other values>

GIS\_STAT\_TYPE

<Null>

APD

DRL

GI

GS

LA

NEW

OPS

PA

PGW

POW

RET

SGW

SOW


TA

TW

WD

WI

WS



1:13,661





JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** NBU 920-12F  
**API Well Number:** 43047501810000  
**Lease Number:** UTU-0144868-B  
**Surface Owner:** INDIAN  
**Approval Date:** 12/30/2008

**Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P. , P.O. Box 173779, Denver, CO 80217

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14.

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**Commingle:**

In accordance with Cause No. 173-14, commingling the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

**Notification Requirements:**

Notify the Division with 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office (801) 733-0983 home

**Reporting Requirements:**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**Approved By:**

A handwritten signature in black ink, appearing to read "Gil Hunt", written over a horizontal line.

For Gil Hunt  
Associate Director, Oil & Gas

RECEIVED  
VERNAL FIELD OFFICE

FORM APPROVED  
OMB No. 1004-0136  
Expires November 30, 2000

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

2008 SEP 18 PM 1

APPLICATION FOR PERMIT TO DRILL OR REENTER

DEPT OF THE INTERIOR  
BUREAU OF LAND MGMT

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER			12. Lease Serial No. UTU-0144868-B	
b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone			13. If Indian, Allottee or Tribe Name UTE TRIBE	
2. Name of Operator KERR-MCGEE OIL & GAS ONSHORE LP			7. If Unit or CA Agreement, Name and No. 891008900A	
3A. Address PO BOX 173779, DENVER, CO 80217-3779		3b. Phone No. (include area code) 720-929-6666		8. Lease Name and Well No. NBU 920-12F
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENW - 1957' FNL, 1922' FWL NAD 83 LAT 40.05193/ LONG 109.61783 At proposed prod. Zone			9. API Well No. 43-047-60181	
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 38 +/- MILES FROM VERNAL, UTAH			10. Field and Pool, or Exploratory NATURAL BUTTES	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1922'		16. No. of Acres in lease 600		11. Sec., T., R., M., or Blk. and Survey or Area SECTION 12, T9S, R20E, SLB&M
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1500' +/-		19. Proposed Depth 10800'		12. County or Parish UINTAH
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4704' KB		22. Approximate date work will start* ASAP		13. State UTAH
23. Estimated duration 10 DAYS				

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- |   |   |
|---|---|
| 1. Well plat certified by a registered surveyor.  | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).   |
| 2. A Drilling Plan.   | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized office. |

25. Signature <i>Raleen White</i>	Name (Printed/Typed) RALEEN WHITE	Date 9/11/2008
Title Sr. Regulatory Analyst		
Approved by (Signature) <i>Stephanie J Howard</i>	Name (Printed/Typed) Stephanie J Howard	Date 9/2/09
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

NOS apd posted 9-22-08  
AFMSS# 99-110053A

RECEIVED  
OCT 08 2009  
DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED

11006M



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4401



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Kerr McGee Oil & Gas Onshore LP	Location:	SWNE, Sec. 12, T9S R20E
Well No:	NBU 920-12F	Lease No:	UTU-0144868-B
API No:	43-047-50181	Agreement:	Natural Buttes Unit

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <u><a href="mailto:ut_vn_opreport@blm.gov">ut_vn_opreport@blm.gov</a></u> .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

**SITE SPECIFIC CONDITIONS OF APPROVAL**

- Additional Stipulations:
- Paint facilities "shadow gray."
- Utilize pit-run/gravel for well pad and access road support.
- Construct surface pipeline according to the BLM's Hydraulic Consideration for Pipeline Crossings of Stream Channels (BLM, 2003) where it crosses the wash.
- Construct access road with a low-water crossing through the wash to accommodate possible flooding. Use pit-run/gravel ant the water crossing.
- If project construction operations are scheduled to occur after December 31, 2009, KMG will conduct additional raptor surveys in accordance with the guidelines specified in the Utah Field Office Guidelines for Raptor Protection for Human and Land Use Disturbances, 2002 and conduct its operations according to applicable seasonal restrictions and spatial offsets.
- If project construction operation are scheduled to occur after April 20, 2010, KMG will conduct additional biological surveys in accordance with the guidelines specified I the USFWS Rare Plant Conservation Measures for Uinta Basin hookless cactus and conduct its operation according to its specifications.

**General Conditions of Approval:**

- A 30' foot corridor right-of-way shall be approved. Upon completion of each pipeline in corridor, they shall be identified and filed with the Ute Tribe.
- A qualified Archaeologist accompanied by a Tribal Technician will monitor trenching construction of pipeline.

- The Ute Tribe Energy & Minerals Department is to be notified, in writing 48 hours prior to construction of pipeline.
- Construction Notice shall be given to the department on the Ute Tribe workdays, which are Monday through Thursday. The Company understands that they may be responsible for costs incurred by the Ute Tribe after hours.
- The Company shall inform contractors to maintain construction of pipelines within the approved ROW's.
- The Company shall assure the Ute Tribe that "ALL CONTRACTORS, INCLUDING SUB-CONTRACTORS, LEASING CONTRACTORS, AND ETC." have acquired a current and valid Ute Tribal Business License and have "Access Permits" prior to construction, and will have these permits in all vehicles at all times.
- You are hereby notified that working under the "umbrella" of a company does not allow you to be in the field, and can be subject to those fines of the Ute Tribe Severance Tax Ordinance.
- Any deviation of submitted APD's and ROW applications the Companies will notify the Ute Tribe and BIA in writing and will receive written authorization of any such change with appropriate authorization.
- The Company will implement "Safety and Emergency Plan." The Company's safety director will ensure its compliance.
- All Company employees and/or authorized personnel (sub-contractors) in the field will have approved applicable APD's and/or ROW permits/authorizations on their person(s) during all phases of construction.
- All vehicular traffic, personnel movement, construction/restoration operations should be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- All personnel should refrain from collecting artifacts, any paleontological fossils, and from disturbing any significant cultural resources in the area.
- The personnel from the Ute Tribe Energy & Minerals Department should be notified should cultural remains from subsurface deposits be exposed or identified during construction. All construction will cease.
- All mitigative stipulations contained in the Bureau of Indian Affairs Site Specific Environmental Assessment (EA) will be strictly adhered.
- Upon completion of Application for Corridor Right-Way, the company will notify the Ute Tribe Energy & Minerals Department, so that a Tribal Technician can verify Affidavit of Completion.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- Kerr McGee and their contractors shall strictly adhere to all operating practices in the SOP along with all Oil and Gas rules and requirements listed in the Code of Federal Regulations and all Federal Onshore Oil and Gas Orders except where variances have been granted.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.



## OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (1/4, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4.

Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0144868-B
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> Ute In
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 920-12F
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1957 FNL 1922 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 12 Township: 09.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047501810000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input checked="" type="checkbox"/> <b>SPUD REPORT</b> Date of Spud: 11/9/2009	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELL LOCATION ON 11/9/2009 AT 12:00 HRS.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> November 10, 2009		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/9/2009	

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP  
Address: P.O. Box 173779  
city DENVER  
state CO zip 80217

Operator Account Number: N 2995

Phone Number: (720) 929-6100

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
4304750181	NBU 920-12F	SENW	12	9S	20E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
B	99999	2910	11/9/2009	11/10/09		
Comments: MIRU PETE MARTIN BUCKET RIG. MVRD = WSMVD SPUD WELL LOCATION ON 11/9/2009 AT 12:00 HRS.						

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
Comments:						

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
Comments:						

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

ANDY LYTLE

Name (Please Print)

Signature

REGULATORY ANALYST

11/9/2009

Title

Date

RECEIVED

NOV 09 2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0144868-B
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> Ute In
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 920-12F
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1957 FNL 1922 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 12 Township: 09.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047501810000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 11/13/2009	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>ALTER CASING</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	<input type="checkbox"/> <b>CASING REPAIR</b>	
	<input type="checkbox"/> <b>CHANGE WELL NAME</b>	
	<input type="checkbox"/> <b>CONVERT WELL TYPE</b>	
	<input type="checkbox"/> <b>NEW CONSTRUCTION</b>	
	<input type="checkbox"/> <b>PLUG BACK</b>	
	<input type="checkbox"/> <b>RECOMPLETE DIFFERENT FORMATION</b>	
	<input type="checkbox"/> <b>TEMPORARY ABANDON</b>	
	<input type="checkbox"/> <b>WATER DISPOSAL</b>	
	<input type="checkbox"/> <b>APD EXTENSION</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> MIRU PROPETRO AIR RIG ON 11/10/2009. DRILLED 12-1/4" SURFACE HOLE TO 2830'. RAN 8-5/8" 28# J-55 SURFACE CASING. PUMP 20 BBLS OF GEL WATER. LEAD CMT W/350 SX HI FILL @ 11.0 PPG, 3.82 YIELD. TAILED CMT W/250 SX CLASS G PREM LITE @ 15.8 PPG, 1.15 YIELD. DROP PLUG ON 101 AND DISPLACE W/170 BBLS OF 8.3# H2O. 10 BBLS OF LEAD TO SURFACE. W/650 PSI OF LIFT @ 5 BBLS/MIN. LAND PLUG 900 PSI AND CHECK FLOAT. FLOAT HELD. TOP OUT #1 W/125 SX CLASS G PREM LITE @ 15.8 PPG, 1.15 YIELD DOWN 1", 2 BBLS OF CMT TO SURFACE. CMT FELL BACK APPROX 150'. WAIT 2 HR AND PUMP TOP OUT #2 W/125 SX OF SAME CMT. CMT TO SURFACE AND STAYED. WORT.		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/13/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0144868-B			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> Ute In			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 920-12F			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1957 FNL 1922 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 12 Township: 09.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047501810000			
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/19/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input checked="" type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER:         </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests to change the surface casing size for this well. The surface casing size is changing FROM: 9-5/8" TO: 8-5/8". Please see the attached drilling program for additional details. If you have any questions, please contact the undersigned. Thank you.					
Accepted by the <b>Utah Division of          Oil, Gas and Mining</b>		<b>Date:</b> <u>November 18, 2009</u> <b>By:</b> <u>Dan K. Quist</u>			
<b>NAME (PLEASE PRINT)</b> Danielle Piernot		<b>PHONE NUMBER</b> 720 929-6156			
<b>TITLE</b> Regulatory Analyst		<b>DATE</b> 11/17/2009			
<b>SIGNATURE</b> N/A		<b>DATE</b> 11/17/2009			

**KERR-McGEE OIL & GAS ONSHORE LP**  
**DRILLING PROGRAM**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP				DATE	November 17, 2009			
WELL NAME	NBU 920-12F				TD	10,800' MD/TVD			
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah		FINISHED ELEVATION	4,688'
SURFACE LOCATION	SE/4 NW/4	1957' FNL	1922' FWL	Sec 12	T 9S	R 20E	BHL		Straight Hole
	Latitude: 40.051930		Longitude: 109.617830		NAD 83				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (MINERALS), Ute Tribe (SURFACE), UDOGM, Tri-County Health Dept.								

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			11"	8-5/8", 28#, J-55, LTC	Air mist
<p>All water flows encountered while drilling will be reported to the appropriate agencies.</p> <p>Green River @ 1,822'</p> <p>Top of Birds Nest Water @ 2,088'</p> <p>Mahogany @ 2,616'</p> <p>Preset f/ GL @ 2,820' MD</p> <p>Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.</p> <p>Mud logging program TBD</p> <p>Open hole logging program from TD - surf csg</p>					
			7-7/8"	4-1/2" 11.6# HCP-110 & I-80 or equivalent BTC/LTC casing	Water/Fresh Water Mud 8.3-12.2 ppg
	Wasatch @	5,284'			
	Mverde @	8,630'			
	MVU2 @	9,521'			
	MVL1 @	10,029'			
	TD @	10,800'			Max anticipated Mud required 12.2 ppg



# KERR-McGEE OIL & GAS ONSHORE LP

## DRILLING PROGRAM

### CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3,390	1,880	437,000
SURFACE	8-5/8"	0 to 2820	28.00	J-55	LTC	0.76*	1.42	5.53
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 9600	11.60	I-80	BTC	1.74	1.04	2.73
						10,690	8,650	279,000
		9600 to 10800	11.60	HCP-110	LTC	2.39	1.26	24.64

\*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 1.91

1) Max Anticipated Surf. Press. (MASP) (Surf Csg) = (Pore Pressure at next csg point - (0.22 psi/ft-partial evac grad x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.2 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MASP 4,353 psi**

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.2 ppg)

0.62 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MABHP 6,729 psi**

### CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	215	60%	15.60	1.18
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	260	0%	15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
			Premium cmt + 2% CaCl				
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	2,320'	Prem cmt + 16% Gel + 10 pps gilsonite	210	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOC				
	TAIL	500	Premium cmt + 2% CaCl	150	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,780'	Premium Lite II + 0.25 pps celloflake +	390	40%	11.00	3.38
			5 pps gilsonite + 10% gel ' + 1% Retarder				
	TAIL	6,020'	50/50 Poz/G + 10% salt + 2% gel	1,470	40%	14.30	1.31
			+ 0.1% R-3				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint for a total of 15 bow spring centralizers.

### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Emile Goodwin

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young


DATE:



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0144868-B			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> Ute In			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 920-12F			
<b>4. LOCATION OF WELL FOOTAGES AT SURFACE:</b> 1957 FNL 1922 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 12 Township: 09.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047501810000			
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/30/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER:         </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests to change the grade of surface drilling pipe for this well. The surface pipe grade is changing FROM: J-55 LT&C TO: IJ-55 LT&C. Please see the attached drilling program for additional details. If you have any questions, please contact the undersigned. Thank you.					
<b>Accepted by the Utah Division of Oil, Gas and Mining</b>		<b>Date:</b> <u>November 25, 2009</u> <b>By:</b> <u>Dan K. Quist</u>			
<b>NAME (PLEASE PRINT)</b> Danielle Piernot		<b>PHONE NUMBER</b> 720 929-6156			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst  <b>DATE</b> 11/24/2009			



COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	November 24, 2009		
WELL NAME	<b>NBU 920-12F</b>					TD	10,800' MD/TVD		
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION	4,688'	
SURFACE LOCATION	SE/4 NW/4	1957' FNL	1922' FWL	Sec 12	T 9S	R 20E		BHL	Straight Hole
	Latitude:	40.051930	Longitude:	109.617830			NAD 83		
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (MINERALS), Ute Tribe (SURFACE), UDOGM, Tri-County Health Dept.								





# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

## CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2820	28.00	IJ-55	LTC	0.76*	1.42	4.41
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 9600	11.60	I-80	BTC	1.74	1.04	2.73
						10,690	8,650	279,000
		9600 to 10800	11.60	HCP-110	LTC	2.39	1.26	24.64

\*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 1.91

1) Max Anticipated Surf. Press. (MASP) (Surf Csg) = (Pore Pressure at next csg point - (0.22 psi/ft-partial evac grad x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.2 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MASP 4,353 psi**

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.2 ppg)

0.62 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MABHP 6,729 psi**

## CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	215	60%	15.60	1.18
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	310	0%	15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
			Premium cmt + 2% CaCl				
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	2,320'	Prem cmt + 16% Gel + 10 pps gilsonite	210	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOC				
	TAIL	500	Premium cmt + 2% CaCl	150	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,780'	Premium Lite II + 0.25 pps celloflake +	390	40%	11.00	3.38
			5 pps gilsonite + 10% gel ' + 1% Retarder				
	TAIL	6,020'	50/50 Poz/G + 10% salt + 2% gel	1,470	40%	14.30	1.31
			+ 0.1% R-3				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint for a total of 15 bow spring centralizers.

## ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Emile Goodwin

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young

DATE:

SUBMIT AS EMAIL

Print Form

BLM - Vernal Field Office - Notification Form

Operator ANADARKO Rig Name/# PIONEER 69  
Submitted By BRAD PEDERSEN Phone Number 435-828-0982  
Well Name/Number NBU 920-12F  
Qtr/Qtr SE/NW Section 12 Township 9S Range 20E  
Lease Serial Number UTU-0144868  
API Number 43-047-50181

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing  
☐ Intermediate Casing  
☐ Production Casing  
☐ Liner  
☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

BOPE

- ☒ Initial BOPE test at surface casing point  
☐ BOPE test at intermediate casing point  
☐ 30 day BOPE test  
☐ Other

Date/Time 12/23/2010 04:00 AM ☒ PM ☐

Remarks TIME IS APPROXAMATE

RECEIVED

DEC 22 2010

DIV. OF OIL, GAS & MINING

SUBMIT AS EMAIL

Print Form

BLM - Vernal Field Office - Notification Form

Operator ANADARKO Rig Name/# PIONEER 69  
Submitted By DALTON KING Phone Number 435-828-0982  
Well Name/Number NBU 920-12F  
Qtr/Qtr SE/NW Section 12 Township 9S Range 20E  
Lease Serial Number UTU-0144868  
API Number 43-047-50181

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing  
☐ Intermediate Casing  
☒ Production Casing  
☐ Liner  
☐ Other

Date/Time 01/05/2011 10:00 AM ☒ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point  
☐ BOPE test at intermediate casing point  
☐ 30 day BOPE test  
☐ Other

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks TIME IS ESTIMATED

RECEIVED

JAN 04 2011

DIV. OF OIL, GAS & MINING



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-0144868-B			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b> Ute In			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 920-12F			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1957 FNL 1922 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SENW Section: 12 Township: 09.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047501810000			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>TYPE OF SUBMISSION</b>  <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:  <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/17/2011	<b>TYPE OF ACTION</b>  <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input checked="" type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> THE SUBJECT WELL WAS PLACED ON PRODUCTION ON MARCH 17, 2011 AT 6:15 P.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.					
<b>Accepted by the          Utah Division of          Oil, Gas and Mining          FOR RECORD ONLY</b>					
<b>NAME (PLEASE PRINT)</b> Gina Becker		<b>PHONE NUMBER</b> 720 929-6086			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst II			
<b>DATE</b> 3/18/2011					

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB No. 1004-0137  
Expires: July 31, 2010

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other										5. Lease Serial No. UTU0144868B
b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr. Other _____										6. If Indian, Allottee or Tribe Name
2. Name of Operator KERR MCGEE OIL & GAS ONSHORE, Mail: gina.becker@anadarko.com										7. Unit or CA Agreement Name and No. UTU63047A
3. Address POBOX 173779 DENVER, CO 80217										8. Lease Name and Well No. NBU 920-12F
3a. Phone No. (include area code) Ph: 720-929-6086										9. API Well No. 43-047-50181
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface SENW 1957FNL 1922FWL 40.051925 N Lat, 109.617832 W Lon At top prod interval reported below SENW 1957FNL 1922FWL 40.051925 N Lat, 109.617832 W Lon At total depth SENW 1957FNL 1922FWL 40.051925 N Lat, 109.617832 W Lon										10. Field and Pool, or Exploratory NATURAL BUTTES
14. Date Spudded 11/09/2009										11. Sec., T., R., M., or Block and Survey or Area Sec 12 T9S R20E Mer SLB
15. Date T.D. Reached 01/03/2011										12. County or Parish UINTAH
16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 03/17/2011										13. State UT
17. Elevations (DF, KB, RT, GL)* 4688 GL										
18. Total Depth: MD 10904 TVD 10901										19. Plug Back T.D.: MD 10821 TVD 10818
20. Depth Bridge Plug Set: MD TVD										
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) ACBL-CHI TRIPLE COMBO-RMTE										22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Directional Survey? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis)
23. Casing and Liner Record (Report all strings set in well)										
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled	
20.000	14.000 STL	36.7		40		28				
12.250	8.625 IJ-55	28.0		2803		850		0		
7.875	4.500 I-80	11.6		9561		1972		300		
7.875	4.500 P110	11.6	9561	10865						
24. Tubing Record										
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)		
2.375	9997									
25. Producing Intervals										
Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status				
A) WASATCH	7904	8448	7904 TO 8448	0.360	43	OPEN				
B) MESAVERDE	8536	10462	8536 TO 10462	0.360	161	OPEN				
C)										
D)										
26. Perforation Record										
27. Acid, Fracture, Treatment, Cement Squeeze, Etc.										
Depth Interval	Amount and Type of Material									
7904 TO 10462	PUMP 9,681 BBLs SLICK H2O & 363,297 LBS SAND									
28. Production - Interval A										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method	
03/17/2011	03/24/2011	24	→	0.0	1900.0	440.0			FLows FROM WELL	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status		
20/64	1498	2280.0	→	0	1900	440		PGW		
28a. Production - Interval B										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status		
			→							

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #107031 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*

RECEIVED  
MAY 13 2011

## 28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

## 28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas(Sold, used for fuel, vented, etc.)  
SOLD

## 30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVERDE	1790 2072 2477 5286 8501	8501 10904			

## 32. Additional remarks (include plugging procedure):

Attached is the chronological well history & final survey. Completion chrono details individual frac stages.

## 33. Circle enclosed attachments:

- |   |                    |               |                       |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.)     | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis   | 7. Other:     |                       |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #107031 Verified by the BLM Well Information System.  
For KERR MCGEE OIL & GAS ONSHORE,L, sent to the Vernal

Name (please print) GINA T. BECKER

Title REGULATORY ANALYST

Signature

(Electronic Submission)

Date 04/25/2011

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\***

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009	Spud Date: 11/10/2009
Project: UTAH-UINTAH		Site: NBU 920-12F	Rig Name No: PIONEER 69/69, PROPETRO/
Event: DRILLING		Start Date: 11/8/2009	End Date: 1/6/2011
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
11/10/2009	15:00 - 18:00	3.00	MIRU	01	B	P		MOVE RIG IN, DRESS CONDUCTOR, INSTALL AIR BOWL, INSTALL BOWIE LINE, RIG UP RIG, RIG UP PUMPS. P/U AIR HAMMER
	18:00 - 20:00	2.00	MIRU	07	A	P		RIG SERVICE, LUBRICATE RIG.
	20:00 - 21:00	1.00	DRLSUR	02	A	P		AIR SPUD 11/10/2009 20:00. AIR HAMMER 44'-120'.
	21:00 - 23:00	2.00	DRLSUR	06	A	P		LD AIR HAMMER AND P/U MUD MOTOR SN 8049. (3RD RUN) MAKE UP 12-1/4" HC507Z SN 7008622 (1ST RUN). P/U 8" INSTALL AIR BOWL RUBBER.
	23:00 - 0:00	1.00	DRLSUR	02	B	P		DRILL 120'-210'. WOB 5-15KK RPM 45, MOTOR RPM 104, GPM 650, ON/OFF PSI-900/1200, UP/DOWN/ROT= 25/25/25
11/11/2009	0:00 - 16:00	16.00	DRLSUR	02	B	P		DRILL 210'-1900' (1690', 105'/HR) WOB 20K RPM 45, MOTOR RPM 104, GPM 650, ON/OFF PSI-1400/1700 UP/DOWN/ROT=68/66/67 FULL CIRC.W NO LOSS. CIRC RESERVE. USE AIR TO HELP CLEAN HOLE ONLY.
	16:00 - 16:30	0.50	DRLSUR	10	A	P		CLEAN HOLE W/ AIR AND SURVEY W/ WIRELINE. 1840'= 1 DEGREE. INC ONLY
	16:30 - 0:00	7.50	DRLSUR	02	B	P		DRILL 1900'-2500' (600', 80'/HR) WOB 22K, RPM 45, MOTOR RPM 104, GPM 650, ON/OFF PSI 1500/1800 UP/DOWN/ROT 70/68/69 FULL CIRC. WITH NO LOSS. NO WATER GAIN. CIRC RESERVE. AIRATE TO CLEAN HOLE.
11/12/2009	0:00 - 4:30	4.50	DRLSUR	02	B	P		DRILL 2500'-2830' (330', 73'/HR) WOB 22K, RPM 45, MOTOR RPM 104, GPM 650, ON/OFF PSI 1500/1800 UP/DOWN/ROT 72/69/70 FULL CIRC. WITH NO LOSS. NO WATER GAIN. CIRC RESERVE. AIRATE TO CLEAN HOLE.
	4:30 - 5:30	1.00	CSG	05	F	P		CLEAN HOLE W/ AIR. FULL RETURNS WHILE CIRC. RESERVE PIT.
	5:30 - 6:00	0.50	DRLSUR	10	A	P		WIRELINE SURVEY 2710'= 1.5 DEGREES INC. ONLY.
	6:00 - 10:00	4.00	CSG	06	D	P		LDDS, LD BHA.
	10:00 - 13:00	3.00	CSG	12	C	P		RUN 65 JTS OF 8-5/8" 28# J-55 CSG W/ LTC 8RD THREADS AND LAND @ 2788' KB, BAFFLE PLATE RAN IN TOP OF SHOE JT 2745' KB. FILL PIPE @ 1000' AND 2000'. RUN 75' OF 1" UNABLE TO RUN ANY MORE.
	13:00 - 13:30	0.50	RDMO	01	E	P		RIG DOWN RIG AND MOVE OUT. ROAD RIG TO NBU 1022-4HT
	13:30 - 17:00	3.50	CSG	12	E	P		TEST LINES TO 2000' PSI, PUMP 45 BBLS OF H2O , PUMP 20 BBLS OF GEL WATER. PUMP 350 (232 BBLS) SX OF 11#, 3.82 YD, 23 GAL SX HI FILL LEAD CEMENT. PUMP 250 SX (51.2 BBLS) OF 15.8#, 1.15 YD, 5 GAL/SK TAIL CEMENT, DROP PLUG ON FLY AND DISPLACE W/ 170 BBLS OF 8.3# H2O, 10 BBLS OF LEAD TO SURFACE W/ 650 PSI OF LIFT @ 5 BBLS/MIN. LAND PLUG 900 PSI AND CHECK FLOAT. FLOAT HELD. PUMP 125 SX (25.6 BBLS) OF 4% CALC 15.8# 1.15 YD, 5 GAL/SK CEMENT DOWN 1" 2 BBLS OF CEMENT TO SURFACE. CEMENT FELL BACK APPROX 150'. WAIT 2 HR AND PUMP 125 SX (25.6 BBLS) OF SAME CEMENT. CEMENT TO SUFACE AND STAYED.
12/21/2010	18:00 - 0:00	6.00	RDMO	01	E	P		RDRT, L/D KELLY ,R/D FLOOR, PUMPS ,PITS, STEAM,SOME ELECTRICAL,WATER, GAS BUSTER, FLARE LINES, MISC



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F		Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING		Start Date: 11/8/2009		End Date: 1/6/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
12/22/2010	0:00 - 7:00	7.00	RDMO	01	E	P		RDRT
	7:00 - 17:30	10.50	MIRU	01	A	P		SAFETY MEETING w/ ALL PERSONEL ON LOCATION. RIG DOWN LOADED OUT THE EQUIPMENT AND MOVED TO THE NBU 920-12F. WE HAD 5 TRUCKS AND 1 FORKLIFT. WE HAD PROBLEMS LOWERING THE DERRICK AND SUB THE HYDRAULIC PUMP WAS NOT OPERATING CORRECTLY. ALSO HAD A TRUCK FROM MOUNTAIN WEST BRAKE DOWN BEFORE ARRIVING ON LOCATION TO MOVE THE CAMPS. WEST ROC MOVED THE CAMPS, TRUCKS ARRIVED @ 6:30 AM AND THE CRANE ARRIVED @ 07:00. TRUCKS LEFT @ 17:30. THE CRANE SHUT DOWN @ SUNDOWN. WE WILL HAVE TO RAISE THE DERRICK AT FIRST LIGHT. THE RIG LOADS ARE ALL SET IN.
	17:30 - 0:00	6.50	MIRU	01	B	P		RIG UP ELCTRIC, BOILER, FLARE LINES, BACKYARD.
								RU PITS, BOILER, AIR LINES, TARPS, FLARE LINES.
12/23/2010	0:00 - 7:00	7.00	MIRU	01	B	P		RAISE THE DERRICK, SCOPE UP THE DERRICK, RU THE FLOOR, PU/ MAKE UP THE KELLY. RIG UP MISC. GROUND EQUIP. CRANE CREW ARRIVED @ 07:00 AND LEFT @ 10:00
	7:00 - 15:30	8.50	MIRU	01	B	P		NU THE BOP AND CHOKE MANIFOLD
	15:30 - 17:30	2.00	DRLPRO	14	A	P		SAFETY MEETING W/ QUICK TEST, TEST FLOOR VALVES, UPPER & LOWER KELLY VALVES, PIPE & BLIND RAMS, INSIDE & OUT SIDE BOP VALVES ,HCR VALVE, CHOKE MANIFOLD, & KILL LINE 250/5 MIN, 5000/ 10 MIN, ANNULAR 250/5 MIN, 2500/ 10 MIN, CASING 1500 F/ 30 MIN , R/D TESTER
	17:30 - 20:00	2.50	DRLPRO	15	A	P		INSTALL WEAR BUSHING, FINISH THE FLOWLINE, STRAP THE BHA
	20:00 - 21:30	1.50	DRLPRO	14	A	P		RU THE LAYDOWN TRUCK, PU THE BHA SCRIBE IT AND PU DP
	21:30 - 0:00	2.50	DRLPRO	06	A	P		PU DP TO 2550'. RD KIMSEY.
12/24/2010	0:00 - 3:30	3.50	DRLPRO	06	A	P		INSTALLED THE KELLY DRIVERS AND THE ROTATING RUBBER.
	3:30 - 4:30	1.00	DRLPRO	14	B	P		TAGGED CEMENT @ 2663' DRILLED CEMENT AND FLOAT EQUIP.
	4:30 - 7:30	3.00	DRLPRO	02	F	P		DRILL F/ 2844'-3833', 990'/9.5HR 104.2'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 95/90/93, ON/OFF 1480/940, DIFF 400-550, SLID 30' @ 360 AZM. STARTED MUD UP @ 3100' VIS/34 WT/9.5
	7:30 - 17:00	9.50	DRLPRO	02	B	P		RIG SERVICE
	17:00 - 17:30	0.50	DRLPRO	07	A	P		DRILL F/ 3833'-4442', 609'/6.5HR 93.7'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 120/95/102, ON/OFF 1525/1000, DIFF 400-550, SLID 25' @ 360 AZM. VIS/32 WT/9.9
	17:30 - 0:00	6.50	DRLPRO	02	B	P		DRILL F/ 4442'-5034', 592'/6HR 98.7'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 125/100/110, ON/OFF 2080/1450, DIFF 400-625, SLID 25' @ 360 AZM. VIS/32 WT/10.4
12/25/2010	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILL F/ 5034'-5603', 569'/5HR 113.8'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 130/110/120, ON/OFF 2100/1475, DIFF 400-550, SLID 15' @ 360 AZM. VIS/37 WT/10.4
	6:00 - 11:00	5.00	DRLPRO	02	B	P		RIG SERVICE
	11:00 - 11:30	0.50	DRLPRO	07	A	P		

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F			Spud Conductor: 11/9/2009				Spud Date: 11/10/2009		
Project: UTAH-UINTAH			Site: NBU 920-12F				Rig Name No: PIONEER 69/69, PROPETRO/		
Event: DRILLING			Start Date: 11/8/2009				End Date: 1/6/2011		
Active Datum: RKB @4,722.00ft (above Mean Sea Level)			UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
	11:30 - 0:00	12.50	DRLPRO	02	B	P		DRILL F/ 5603'-6520', 917'/5HR 73.4'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 135/125/130, ON/OFF 2150/1550, DIFF 400-600, VIS/37 WT/10.6	
12/26/2010	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILL F/ 6520'-6994', 474'/6HR 79'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 145/135/140, ON/OFF 2150/1570, DIFF 400-600, VIS/37 WT/10.7	
	6:00 - 14:00	8.00	DRLPRO	02	B	P		DRILL F/ 6994'-7500', 506'/8HR 63.3'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 155/140/150, ON/OFF 2275/1700, DIFF 400-600, VIS/37 WT/11.0 RAISING WEIGHT FOR SLOUGHING	
	14:00 - 14:30	0.50	DRLPRO	07	A	P		RIG SERVICE	
	14:30 - 0:00	9.50	DRLPRO	02	B	P		DRILL F/ 7500'-7840', 340'/9.5HR 35.8'/HR',SLID 9' @ 340 AZM, 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 160/145/155, ON/OFF 2450/1760, DIFF 500-700, VIS/39 WT/11.3	
12/27/2010	0:00 - 5:30	5.50	DRLPRO	02	B	P		DRILL F/ 7840'-7990', 150'/5.5HR 27.3'/HR', 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 160/145/155, ON/OFF 2150/1760, DIFF 300-450, VIS/40 WT/11.5	
	5:30 - 6:00	0.50	DRLPRO	22	O	P		MAINTANANCE/ ADJ. THE BRAKES	
	6:00 - 18:00	12.00	DRLPRO	02	B	P		DRILL F/ 7990'-8332', 342'/12HR 28.5'/HR, 20-24K WOB, RPM/50-55, MMRPM/91, SPM 120, GPM 454, UP/SO/ROT 165/155/150, ON/OFF 2080/1780, DIFF 250-450, VIS/40 WT/11.8 LCM 1%	
	18:00 - 0:00	6.00	DRLPRO	02	B	P		DRILL F/ 8332'-8480', 148'/6HR 24.7'/HR,18-24K WOB, RPM/50-55, MMRPM/91, SPM 120/115, GPM 454/436, UP/SO/ROT 173/150/163, ON/OFF 2100/1800, DIFF 250-400, VIS/40 WT/11.9 LCM 3%	
12/28/2010	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILL F/ 8480'-8607', 127'/6HR 21.2'/HR,18-24K WOB, RPM/50-55, MMRPM/87, SPM 120/115, GPM 454/436, UP/SO/ROT 173/150/163, ON/OFF 2100/1800, DIFF 250-400, VIS/42 WT/11.9 LCM 3%	
	6:00 - 14:00	8.00	DRLPRO	02	B	P		DRILL F/ 8607'-8828', 221'/8HR 27.6'/HR,18-24K WOB, RPM/50-55, MMRPM/87, SPM 120/115, GPM 436, UP/SO/ROT 173/150/163, ON/OFF 2300/1850, DIFF 250-400, VIS/44 WT/12.0 LCM 3%	
	14:00 - 14:30	0.50	DRLPRO	07	A	P		RIG SERVICE	
	14:30 - 16:00	1.50	DRLPRO	02	B	P		DRILL F/ 8828'-8860', 32'/1.5HR 21.3'/HR,18-24K WOB, RPM/50-55, MMRPM/91, SPM 120/115, GPM 436, UP/SO/ROT 185/155/168, ON/OFF 2300/1850, DIFF 250-400, VIS/40 WT/12.0 LCM 3%	
	16:00 - 16:30	0.50	DRLPRO	05	C	P		CIRC.PUMPED A PILL	
	16:30 - 18:30	2.00	DRLPRO	06	A	P		TOH FOR BIT	
	18:30 - 19:30	1.00	DRLPRO	22	A	X		WE HIT A TIGHT SPOT @ 5200' IT PULLED 40 K OVER. WORKING TIGHT PIPE	
	19:30 - 0:00	4.50	DRLPRO	22	A	X		BROKE OFF THE CONNECTION (20' ABOVE THE FLOOR). WE SLACKED ALL THE WEIGHT OFF WHILE GETTING EQUIP TO CIRC. AND THE PIPE FELL FREE AFTER 20 MIN. SLACKED OFF TO THE FLOOR PU THE KELLY CIRCULATED. WE WERE CIRC. THE HOLE TO BACK REAM AND CLEAN UP THE HOLE. WE PULLED INTO THE TIGHT SPOT W/ 25K OVER AND BECAME STUCK AGAIN. WORKED THE PIPE DOWN W/ MINOR SUCESS. HAD TO BRAKE THE KELLY ABOVE THE FLOOR TO STAND IT BACK.	

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F		Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING		Start Date: 11/8/2009		End Date: 1/6/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
12/29/2010	0:00 - 3:00	3.00	DRLPRO	22	A	X		5190' DEPTH PU THE SUFACE JARS AND ATTEMPTED TO USE THEM. THE JARS WERE INOPERABLE. RD THE JARS. THE BREAK WAS 20' OFF OF THE FLOOR.
	3:00 - 6:00	3.00	DRLPRO	22	A	X		WORKING THE PIPE AND CIRCULATING. BROUGHT THE MUD WT TO 12.4 46/VIS 4% LCM WHILE WAITING FOR ANOTHER SET OF JARS
	6:00 - 14:00	8.00	DRLPRO	22	A	X		PU NEW SURFACE JARS. JARING AND WORKING PIPE FROM 5190' TO 5069'. USED THE JARS TO LD 6 MORE SINGLES THAT WERE STILL STICKY.
	14:00 - 14:30	0.50	DRLPRO	23		X		INSPECTED THE DERRICK AND PREPARED TO TOH
	14:30 - 16:00	1.50	DRLPRO	22	A	X		WE HAD TO PICK THE JARS BACK UP AND LD 5 MORE SINGLES TO 4740'
	16:00 - 20:00	4.00	DRLPRO	06	A	P		TOH AND XO A MUD MOTOR AND BIT. CHECKED THE MWD TOOLS (TESTED OK)
	20:00 - 0:00	4.00	DRLPRO	06	A	P		MADE UP THE BHA SCRIBED THE ASSEMBLY AND TIH.
12/30/2010	0:00 - 2:30	2.50	DRLPRO	09	A	P		CUT AND SLIPPED 110' OF DRILLING LINE.
	2:30 - 3:30	1.00	DRLPRO	06	A	P		TIH TO 4873'
	3:30 - 6:30	3.00	DRLPRO	03	A	X		WASHED AND REAMED F/ 4873' TO 5291' STICKY SPOTS.
	6:30 - 8:00	1.50	DRLPRO	06	A	X		SET THE KELLY BACK AND TIH TO 6960'
	8:00 - 10:00	2.00	DRLPRO	03	A	X		BROKE DOWN 3 STANDS OF DP AND REAMED 4 JTS F/6960' TO 7030'. BRIDGES SET THE KELLY BACK
	10:00 - 11:00	1.00	DRLPRO	06	A	P		TIH TO BOTTOM
	11:00 - 11:30	0.50	DRLPRO	03	D	P		WASH AND REAM 60' TO BOTTOM
	11:30 - 16:30	5.00	DRLPRO	02	B	P		DRILL F/ 8860'-9018', 158'/5HR 31.6'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 180/160/174, ON/OFF 2300/2000, DIFF 250-400, VIS/40 WT/12.4 LCM/ 3%
	16:30 - 17:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	17:00 - 0:00	7.00	DRLPRO	02	B	P		DRILL F/ 9018'-9252', 234'/7HR 33.4'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 180/160/174, ON/OFF 2300/2010, DIFF 250-400, VIS/40 WT/12.5 LCM/ 4%
12/31/2010	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILL F/ 9252'-9492', 240'/6HR, 40'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 180/165/177, ON/OFF 2350/2010, DIFF 250-400, VIS/40 WT/12.5 LCM/ 4%
	6:00 - 16:30	10.50	DRLPRO	02	B	P		DRILL F/ 9492'-9871', 379'/10.5HR, 36.1'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 188/175/182, ON/OFF 2435/2005, DIFF 300-450, VIS/40 WT/12.5 LCM/ 4%
	16:30 - 17:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	17:00 - 0:00	7.00	DRLPRO	02	B	P		DRILL F/ 9871'-10092', 221'/7HR, 31.6'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 189/170/184, ON/OFF 2350/2050, DIFF 250-400, VIS/43 WT/12.5 LCM/ 4%
	0:00 - 9:00	9.00	DRLPRO	02	B	P		DRILL F/ -10092'-10272', 180'/9HR, 20'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 189/170/184, ON/OFF 2350/2050, DIFF 250-400, VIS/43 WT/12.5 LCM/ 4%
1/1/2011	9:00 - 12:30	3.50	DRLPRO	06	A	P		TOH TO 6670'
	12:30 - 13:30	1.00	DRLPRO	03	A	X		WORK A TIGHT SPOT. PU THE KELLY AND BACK REAM THROUGH IT.
	13:30 - 20:00	6.50	DRLPRO	06	A	P		SET THE KELLY BACK AND TOH. LD THE MWD TOOLS,

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F			Spud Conductor: 11/9/2009				Spud Date: 11/10/2009	
Project: UTAH-UINTAH			Site: NBU 920-12F				Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING			Start Date: 11/8/2009		End Date: 1/6/2011			
Active Datum: RKB @4,722.00ft (above Mean Sea Level)			UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
1/2/2011	20:00 - 0:00	4.00	DRLPRO	06	A	P		CHANGED OUT THE MM AND BIT.TIH TO THE CASING SHOE. 2840'
	0:00 - 2:00	2.00	DRLPRO	08	A	Z		FROZEN AIR AND FLUID LINES
	2:00 - 2:30	0.50	DRLPRO	05	A	P		FILL THE DP @ THE SHOE
	2:30 - 4:30	2.00	DRLPRO	06	A	P		TIH TO 6797' FILLED DP @ 5900'
	4:30 - 7:30	3.00	DRLPRO	03	A	S		PU THE KELLY WASH/REAM TIGHT SPOT FROM 6797'-6870'. DRAIN UP THE KELLY AND HANG IT BACK.
	7:30 - 12:00	4.50	DRLPRO	06	A	P		TIH TO BOTTOM, PU THE KELLY AND BREAK CIRCULATION
	12:00 - 12:30	0.50	DRLPRO	03	D	P		WASH 60' TO BOTTOM
	12:30 - 17:00	4.50	DRLPRO	02	B	P		DRILL F/ 10272'-10456', 184'/4.5HR,40.9'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 195/175/183, ON/OFF 2400/2050, DIFF 250-400, VIS/43 WT/12.5 LCM/ 5% RIG SERVICE
1/3/2011	17:00 - 17:30	0.50	DRLPRO	07	A	P		DRILL F/ 10456'-10680', 224'/6HR,34.5'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 198/175/191, ON/OFF 2350/2080, DIFF 250-300, VIS/44 WT/12.8 LCM/ 5% 10' FLARE @ 10772'
	17:30 - 0:00	6.50	DRLPRO	02	B	P		DRILL F/ 10680'-10857', 177'/7HR,25.3'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 200/185/195, ON/OFF 2350/2080, DIFF 200-300, VIS/44 WT/12.7 LCM/ 5% RIG SERVICE
	0:00 - 7:00	7.00	DRLPRO	02	B	P		DRILL F/ 10857'-10904', 18'/2HR,9'/HR, 18-24K WOB, RPM/50-55, MMRPM/70, SPM/115, GPM 436, UP/SO/ROT 200/185/195, ON/OFF 2240/2080, DIFF 180-250, VIS/44 WT/12.8 LCM/ 5% 10' FLARE @ BOTTOMS UP F/ RIG SERV.
	7:00 - 7:30	0.50	DRLPRO	07	A	P		CIRCULATE AND CONDITION THE MUD. RAISED THE MUD WT TO 13.0 PUMPED A 60BBL. SLUG MADE A WIPER TRIP TO THE CASING SHOE. HIT 1 BRIDGE @ 9234'
	7:30 - 9:30	2.00	DRLPRO	02	B	P		CIRCULATE AND COND. F/ LOGS
	9:30 - 12:00	2.50	DRLPRO	05	C	P		CIRC/COND. F/ LOGS. PUMPED A 60 BBL. 14.5 SLUG 44/VIS 13.0/MW 20' FLARE BOTTOMS UP TOH FOR LOGS, NO HOLE PROBLEMS
	12:00 - 23:00	11.00	DRLPRO	06	E	P		RIGGED UP BAKER ATLAS. THEY BLEW A HYDRAULIC LINE. RD THE LOGGING TRUCK. CONTACTED DENVER AND GOT THE OK TO CONTINUE WITHOUT LOGS.
	23:00 - 0:00	1.00	DRLPRO	05	C	P		SAFETY MEETING AND TIH TO 2800'
1/4/2011	0:00 - 1:00	1.00	DRLPRO	05	C	P		CUT AND SLIP 120' DRLG LINE
	1:00 - 8:00	7.00	DRLPRO	06	B	P		TIH STRAPPED DP. FILLED DP @ 6500' WASHED DOWN THE LAST JT ADJUSTED TD DEPTH
	8:00 - 9:30	1.50	DRLPRO	11	D	Z		CIRC./COND THE MUD, RU KIMSEY LD TRUCK, AND PUMPED OUR WEIGHTED PILL. 44/VIS 13.1/MW 10' FLARE BOTTOMS UP
	9:30 - 13:30	4.00	DRLPRO	06	A	P		SAFETY MEETING W/ KIMSEY, LDDP
	13:30 - 15:00	1.50	DRLPRO	09	A	P		LDDP , BREAK KELLY ,L/D BHA , PULL WEAR RING
1/5/2011	15:00 - 19:30	4.50	DRLPRO	06	A	P		S/M W/ KIMZEY R/U CASERS
	19:30 - 22:00	2.50	DRLPRO	05	A	P		RUN 30 JTS P110 ,227 JTS I80 ( TOTAL 257 JTS) SHOE DEPTH 10887', FLOAT @ 10849' MARKERS @ 5279' & 8536'
	22:00 - 0:00	2.00	DRLPRO	06	A	P		CIRC F/ CEMENT, R/D KIMZEY
	0:00 - 9:00	9.00	DRLPRO	06	A	P		
	9:00 - 10:00	1.00	DRLPRO	12	A	P		
	10:00 - 18:00	8.00	DRLPRO	12	C	P		
	18:00 - 20:30	2.50	DRLPRO	05	D	P		



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F			Spud Conductor: 11/9/2009			Spud Date: 11/10/2009				
Project: UTAH-UINTAH			Site: NBU 920-12F				Rig Name No: PIONEER 69/69, PROPETRO/			
Event: DRILLING			Start Date: 11/8/2009					End Date: 1/6/2011		
Active Datum: RKB @4,722.00ft (above Mean Sea Level)			UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0							
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation		
	20:30 - 0:00	3.50	DRLPRO	12	E	P		S/M W/ BJ SERVICES, R/U & PUMP 40 BBL WATER, 700 SX 13.1# ,1.73 YLD LEAD ,1272 SX 14.3#, 1.31 YLD TAIL, DISPLACED W/ 168 BBLS CLAY TREAT WATER, FINAL LIFT 3551, BUMPED PLUG @ 4295,FLOATS HELD , 30 BBLS SPACER BACK,NO CEMENT TO SURFACE ,EST TOP OF TAIL @ 4000' ,R/D CEMENTERS		
1/6/2011	0:00 - 4:00	4.00	DRLPRO	14	A	P		FLUSH STACK SET C-22 SLIPS @ 116K, NIPPLE DOWN,CUT OFF CASING, CLEAN PITS RELEASE RIG @ 0400 1/6/2011TO NBU 920-12G		

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F		Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING		Start Date: 11/8/2009		End Date: 1/6/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	4:00 - 4:00	0.00	DRLPRO					<p>CONDUCTOR CASING: Cond. Depth set: Cement sx used:</p> <p>SPUD DATE/TIME: 11/10/2009 20:00</p> <p>SURFACE HOLE: Surface From depth: 14 Surface To depth: 2,844 Total SURFACE hours: 29.00 Surface Casing size: 8 5/8 # of casing joints ran: 65 Casing set MD: 2,788.0 # sx of cement: LEAD/350 TAIL/250 TOP OFF/250 Cement blend (ppg:) LEAD 11.0 TAIL/15.9 TO/15.8 Cement yield (ft3/sk): LEAD/3.82 TAIL/1.15 # of bbls to surface: Describe cement issues: Describe hole issues:</p> <p>PRODUCTION: Rig Move/Skid start date/time: 12/21/2010 18:00 Rig Move/Skid finish date/time: 12/22/2010 17:30</p> <p>Total MOVE hours: 23.5 Prod Rig Spud date/time: 12/24/2010 14:30 Rig Release date/time: 1/6/2011 4:00 Total SPUD to RR hours: 301.5 Planned depth MD 10,900 Planned depth TVD 10,904 Actual MD: 10,904 Actual TVD: 10,901 Open Wells \$: \$1,011,263 AFE \$: \$1,075,667 Open wells \$/ft: \$92.74</p> <p>PRODUCTION HOLE: Prod. From depth: 2,844 Prod. To depth: 10,904 Total PROD hours: 166.5 Log Depth: N/A Float Collar Top Depth: 10847.49 Production Casing size: 5.5 ,11.6 # of casing joints ran: 30 P110 ,227 I 80 Casing set MD: 10,887.4 Stage 1 # sx of cement: 700 LEAD , 1272 TAIL Cement density (ppg:) 13.1 LEAD ,14.3 TAIL Cement yield (ft3/sk): 1.73 LEAD, 1.31 TAIL Stage 2 # sx of cement: Cement density (ppg): Cement yield (ft3/sk): Top Out Cmt # sx of cement: Cement density (ppg): Cement yield (ft3/sk): Est. TOC (Lead &amp; Tail) or 2 Stage : Describe cement issues: NO CEMENT TO SURFACE Describe hole issues:</p> <p>DIRECTIONAL INFO:</p>

## US ROCKIES REGION

**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009				
Project: UTAH-UINTAH		Site: NBU 920-12F		Rig Name No: PIONEER 69/69, PROPETRO/				
Event: DRILLING		Start Date: 11/8/2009		End Date: 1/6/2011				
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
								KOP: Max angle: Departure: Max dogleg MD:

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009	Spud Date: 11/10/2009
Project: UTAH-UINTAH		Site: NBU 920-12F	Rig Name No: SWABBCO 1/1
Event: COMPLETION		Start Date: 3/7/2011	End Date: 3/17/2011
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
3/7/2011	6:30 - 7:16	0.77	COMP	48		P		HSM & JSA W/SUPERIOR & CUTTERS.
	7:16 - 8:12	0.93	COMP	37	B	P		07:16 - OPEN WELL. WHP = 0 PSI. PERF STG 1) PU 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE, 90 & 120 DEG PHASING. RIH & PERF MV F/ 10460-62, 3 SPF, 6 HOLES. 10424-26, 3 SPF, 6 HOLES. 10378-79, 4 SPF, 4 HOLES. 10314-16, 3 SPF, 6 HOLES. 22 HOLES. POOH, X-OVER FOR FRAC CREW. WHP = 0 PSI. PT SURFACE EQUIP. TO 8000 PSI. 09:11 OPEN WELL FRAC STG 1) WHP 178 PSI, BRK DWN 4.7 BPM @ 5046 PSI. ISIP 3416 PSI, FG 0.77, PMP 6 BBLS 15% HCL, PMP 160 BBLS 10/M SCALE INHIBITOR. PUMP 255 BBLS @ 39 BPM @ 06212000 PSI, 17/22 PERFS OPEN = 77%
	9:11 - 9:40	0.48	COMP	36	E	P		MP 6708 PSI, MR 50.8 BPM, AP 6287 PSI, AR 40.5 BPM, ISIP 3612 PSI, FG 0.79, NPI 196 PSI. PMP 897 BBLS SW & 21,070 LBS OF 30/50 SND & 5,656 LBS OF 20/40 SLC SND. TOTAL PROP 26,726 LBS, SWI, 09:40 X-OVER FOR WL. 09:45 OPEN WELL. PERF STG 2) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 10,277', P/U & PERF MV F/ 10246-47, 4 SPF, 4 HOLES. 10105-07, 3 SPF, 6 HOLES. 10082-83, 4 SPF, 4 HOLES. 10050-51, 4 SPF, 4 HOLES. 10020-21, 4 SPF, 4 HOLES. 22 HOLES. POOH, X-OVER FOR FRAC CREW.
	9:45 - 10:52	1.12	COMP	37	B	P		10:59 OPEN WELL FRAC STG 2) WHP 247 PSI, BRK DWN 4.8 BPM @ 4153 PSI. ISIP 3365 PSI, FG 0.77. PUMP 133 BBLS @ 35.9 BPM @ 6424 PSI. 14/22 PERFS OPEN = 64%
	10:59 - 11:29	0.50	COMP	36	E	P		MP 7013 PSI, MR 51.3 BPM, AP 6519 PSI, AR 43.9 BPM, ISIP 3482 PSI, FG 0.78, NPI 117 PSI. PMP 1051 BBLS SW & 34,606 LBS OF 30/50 SND & 5,633 LBS OF 20/40 SLC SND. TOTAL PROP 40,239 LBS, SWI, 11:29 X-OVER FOR WL. PERF STG 3) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 9,994', P/U & PERF MV F/ 9962-64, 4 SPF, 8 HOLES. 9902-03, 4 SPF, 4 HOLES. 9862-64, 3 SPF, 6 HOLES. 9683-84, 4 SPF, 4 HOLES. 22 HOLES. POOH, X-OVER FOR FRAC CREW.
	11:35 - 12:40	1.08	COMP	37	B	P		

US ROCKIES REGION  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F			Rig Name No: SWABBCO 1/1
Event: COMPLETION		Start Date: 3/7/2011		End Date: 3/17/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	12:45 - 13:08	0.38	COMP	36	E	P		12:45 OPEN WELL FRAC STG 3) WHP 375 PSI, BRK DWN 4.7 BPM @ 4931 PSI. ISIP 3416 PSI, FG 0.79. PUMP 98 BBLs @ 39.7 BPM @ 6362 PSI. 16/22 PERFS OPEN = 75%  MP 6800 PSI, MR 51.7 BPM, AP 6299 PSI, AR 46.5 BPM, ISIP 3219 PSI, FG 0.77, NPI (-197) PSI. PMP 800 BBLs SW & 24,416 LBS OF 30/50 SND & 5,089 LBS OF 20/40 SLC SND. TOTAL PROP 29,505 LBS, SWI, 13:08 X-OVER FOR WL.
	13:13 - 14:09	0.93	COMP	37	B	P		PERF STG 4) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 9,633, P/U & PERF MV F/ 9590-91, 4 SPF, 4 HOLES. 9564-65, 4 SPF, 4 HOLES. 9434-36, 3 SPF, 6 HOLES. 9326-27, 4 SPF, 4 HOLES. 9292-93, 4 SPF, 4 HOLES. 22 HOLES. POOH, X-OVER FOR FRAC CREW.
	14:13 - 14:49	0.60	COMP	36	E	P		14:13 OPEN WELL FRAC STG 4) WHP 360 PSI, BRK DWN 4.7 BPM @ 6064 PSI. ISIP 3096 PSI, FG 0.77. PUMP 172 BBLs @ 39.7 BPM @ 6645 PSI. 14/22 PERFS OPEN = 64%  MP 7166 PSI, MR 51 BPM, AP 6104 PSI, AR 47.3 BPM, ISIP 3325 PSI, FG 0.79, NPI 229 PSI. PMP 1287 BBLs SW & 46,592 LBS OF 30/50 SND & 5,630 LBS OF 20/40 SLC SND. TOTAL PROP 52,222 LBS, SWI, 14:49 X-OVER FOR WL.
	14:55 - 15:47	0.87	COMP	37	B	P		PERF STG 5) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 9,204', P/U & PERF MV F/ 9172-74, 3 SPF, 6 HOLES. 9149-51, 3 SPF, 6 HOLES. 9080-82, 3 SPF, 6 HOLES. 9036-38, 3 SPF, 6 HOLES. 24 HOLES. POOH, X-OVER FOR FRAC CREW.
	15:50 - 16:13	0.38	COMP	36	E	P		15:50 OPEN WELL FRAC STG 2) WHP 371 PSI, BRK DWN 4.7 BPM @ 6259 PSI. ISIP 3360 PSI, FG 0.81. PUMP 99 BBLs @ 46.9 BPM @ 6374 PSI. 20/24 PERFS OPEN = 84%  MP 6995 PSI, MR 50.7 BPM, AP 6128 PSI, AR 47.6 BPM, ISIP 3235 PSI, FG 0.79, NPI (-125) PSI. PMP 814 BBLs SW & 24,607 LBS OF 30/50 SND & 4,879 LBS OF 20/40 SLC SND. TOTAL PROP 29,486 LBS, SWI, 16:13 X-OVER FOR WL.



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F			Rig Name No: SWABBCO 1/1
Event: COMPLETION		Start Date: 3/7/2011		End Date: 3/17/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	16:18 - 17:15	0.95	COMP	37	B	P		PERF STG 6) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 8,950' P/U & PERF MV F/ 8912-14, 4 SPF, 8 HOLES. 8838-40, 4 SPF, 8 HOLES. 8800-02, 4 SPF, 8 HOLES. 24 HOLES. POOH, X-OVER FOR FRAC CREW.
3/15/2011	6:30 - 6:50	0.33	COMP	48		P		SWI - SDFN. FREEZE PROTECT WH. PROP TO FRAC STG 6 IN AM.
	6:50 - 7:13	0.38	COMP	36	E	P		HSM & JSA W/SUPERIOR & CUTTERS 06:50 OPEN WELL FRAC STG 6) WHP 2109 PSI, BRK DWN 4.6 BPM @ 4953 PSI. ISIP 2921 PSI, FG 0.77. PUMP 109 BBLs @ 47.4 BPM @ 6350 PSI. 18/24 PERFS OPEN = 76%
	7:28 - 8:43	1.25	COMP	37	B	P		MP 6839 PSI, MR 52.1 BPM, AP 5860 PSI, AR 49.2 BPM, ISIP 3022 PSI, FG 0.78, NPI 101 PSI. PMP 867 BBLs SW & 27,258 LBS OF 30/50 SLD & 5,605 LBS OF 20/40 SLC SLD. TOTAL PROP 32,863 LBS, SWI, 07:13 X-OVER FOR WL. PERF STG 7) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 8,759', [LOST WT @ 8739'. PICK UP PMP 1000 GAL. RIH & SET CBP @ 8,759']. P/U & PERF MV F/ 8728-29, 4 SPF, 4 HOLES. 8699-8700, 4 SPF, 4 HOLES. 8680-81, 3 SPF, 3 HOLES. 8640-41, 3 SPF, 3 HOLES. 8613-14, 3 SPF, 3 HOLES. 8562-63, 4 SPF, 4 HOLES. 8536-37, 4 SPF, 4 HOLES. 25 HOLES. POOH, X-OVER FOR FRAC CREW.
	8:47 - 9:47	1.00	COMP	36	E	P		08:47 OPEN WELL FRAC STG 2) WHP 359 PSI, BRK DWN 4.7 BPM @ 3491 PSI. ISIP 2042 PSI, FG 0.68. PUMP 319 BBLs @ 048.70 BPM @ 6235 PSI. 16/25 PERFS OPEN = 64% [LOST INLINE DENSO @ 1870 BBLs PMPD-74% JOB PMPD] MP 6785 PSI, MR 51.7 BPM, AP 5546 PSI, AR 48 BPM, ISIP 2729 PSI, FG 0.75, NPI 687 PSI. PMP 2525 BBLs SW & 94,366 LBS OF 30/50 SLD & 5,818 LBS OF 20/40 SLC SLD. TOTAL PROP 100,184 LBS, SWI, 09:47 X-OVER FOR WL.
	9:55 - 10:40	0.75	COMP	37	B	P		PERF STG 8) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 8,486', P/U & PERF WASATCH F/ 8446-48, 4 SPF, 8 HOLES. 8380-82, 3 SPF, 6 HOLES. 8332-34, 4 SPF, 8 HOLES. 22 HOLES. POOH, X-OVER FOR FRAC CREW.

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F		Rig Name No: SWABBCO 1/1	
Event: COMPLETION		Start Date: 3/7/2011		End Date: 3/17/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)		UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	10:56 - 11:41	0.75	COMP	36	E	P		10:56 OPEN WELL FRAC STG 8) WHP 301 PSI, BRK DWN 4.7 BPM @ 4130 PSI. ISIP 2434 PSI, FG 0.73. PUMP 84 BBLs @ 37.7 BPM @ 5295 PSI. 15/22 PERFS OPEN = 68% [65 BBL PMPD - SD - LEAK ON CHICKSAN - REPLACE - DWN 23 MIN. RESTART PAD] MP 6829 PSI, MR 50.5 BPM, AP 5998 PSI, AR 47.7 BPM, ISIP 2942 PSI, FG 0.79, NPI 508 PSI. PMP 800 BBLs SW & 22,907 LBS OF 30/50 SLD & 5,090 LBS OF 20/40 SLC SLD. TOTAL PROP 27,997 LBS, SWI, 11:41 X-OVER FOR WL.
	11:50 - 12:41	0.85	COMP	37	B	P		PERF STG 9) PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, 0.36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8,166', P/U & PERF WASATCH F/ 8124-27, 3 SPF, 9 HOLES. 7904-08, 3 SPF, 12 HOLES. 21 HOLES. POOH, X-OVER FOR FRAC CREW.
	12:54 - 13:10	0.27	COMP	36	E	P		12:54 OPEN WELL FRAC STG 9) WHP 280 PSI, BRK DWN 4.8 BPM @ 5662 PSI. ISIP 2031 PSI, FG 0.69. PUMP 85 BBLs @ 43.4 BPM @ 6505 PSI. 13/21 PERFS OPEN = 62%  MP 6740 PSI, MR 51.3 BPM, AP 6315 PSI, AR 48.1 BPM, ISIP 2628 PSI, FG 0.77, NPI 597 PSI. PMP 640 BBLs SW & 16,787 LBS OF 30/50 SLD & 7,288 LBS OF 20/40 SLC SLD. TOTAL PROP 24,075 LBS, SWI, 13:10 X-OVER FOR WL.
	13:18 - 14:10	0.87	COMP	34	I	P		KILL PLG) PU 4 1/2 8K HALCO CBP, RIH SET CBP @ 7,854'. POOH & LD TOOLS. SWI - RD CUTTERS WL & SUPERIOR FRAC. 14:10 SDFN. PREP WELL TO RIH W/BHA & D/O CBPs.  SWI - SDFD. PREP TO BRING IN SERVICE UNIT TO D/O CBPs.  TOTAL WATER USED 9,681 BBLs TOTAL PROPANT SAND USED 363,297 LBS TOTAL SCALE INHIBITOR USED 990 GAL TOTAL BIOCIDES USED 190 GAL
3/16/2011	7:00 - 7:30	0.50	COMP	48		P		HSM, MOVEING & RIGGING UP RIG & EQUIP.
	7:30 - 10:30	3.00	COMP	30	A	P		MIRU F/ NBU 920-12H, ND FV, NU BOPS, RU FLOOR & TBG EQUIP.( LOCKED SURFACE VALVE OPEN.)
	10:30 - 16:30	6.00	COMP	31	I	P		TALLY & PU 37/8 BIT, POBS, 1.875 X/N & 248 JTS 23/8 L-80 TBG OFF FLOAT. EOT @ 7842 ', RU DRLG EQUIP, PREP TO D/O IN AM. SWI SDFN.
3/17/2011	7:00 - 7:30	0.50	COMP	48		P		HSM, LANDING TBG & ND BOPS & NU WH.

US ROCKIES REGION  
**Operation Summary Report**

Well: NBU 920-12F		Spud Conductor: 11/9/2009		Spud Date: 11/10/2009	
Project: UTAH-UINTAH		Site: NBU 920-12F			Rig Name No: SWABBCO 1/1
Event: COMPLETION		Start Date: 3/7/2011		End Date: 3/17/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)			UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:30 - 17:30	10.00	COMP					<p>BROKE CIRC CONVENTIONAL TEST BOPS TO 3,000# CHANGED OUT RAMS, RIH.</p> <p>C/O 10' SAND TAG 1ST PLUG @ 7854' DRL PLG IN 10 MIN 200# PSI INCREASE RIH.</p> <p>C/O 35' SAND TAG 2ND PLUG @ 8166' DRL PLG IN 11 MIN 1200# PSI INCREASE RIH</p> <p>C/O 40' SAND TAG 3RD PLUG @ 8486' DRL PLG IN 20 MIN 900# PSI INCREASE RIH</p> <p>C/O 25' SAND TAG 4TH PLUG @ 8759' DRL PLG IN 10 MIN 1400# PSI INCREASE RIH</p> <p>C/O 32' SAND TAG 5TH PLUG @ 8950' DRL PLG IN 5 MIN 500# PSI INCREASE RIH</p> <p>C/O 30' SAND TAG 6TH PLUG @ 9204' DRL PLG IN 5 MIN 700# PSI INCREASE RIH</p> <p>C/O 40' SAND TAG 7TH PLUG @ 9633' DRL PLG IN 5 MIN 500# PSI INCREASE. RIH WAIT FOR TBG TO ARIVE 2 HRS</p> <p>C/O 30' SAND TAG 8TH PLUG @ 9994' DRL PLG IN 5 MIN 800# PSI INCREASE RIH</p> <p>C/O 30' SAND TAG 9TH PLUG @ 10,277' DRL PLG IN 4 MIN 1000# PSI INCREASE. RIH</p> <p>C/O TO @ 10.565' CIRC CLEAN, RACK OUT SWIVEL. L/D 18 JTS, LAND TBG ON 316 JTS 23/8 L-80. RD FLOOR, ND BOPS NU WH. PUMP OFF BIT, LET WELL SET FOR 30 MIN FOR BIT TO FALL. TURN WELL OVER TO FB CREW. SDFN SICP = 2100    FTP = 100</p> <p>KB = 13' HANGER 41/16 = .83' 316 JTS 23/8 L-80 = 9981.03'    ( SURFAC VALVE OPEN ) 1.875 X/N &amp; POBS = 2.20' EOT @ 9997.06'</p> <p>TWTR = 9991 BBLS TWR = 1500 BBLS TWLTR = 8491    BBLS</p> <p>348 JTS HAULED OUT 315 LANDED 33 TO RETURN WELL TURNED TO SALES @ 1800 HR ON 3/17/11 - 650 MCFD, 2160 BWPD, CP 2300#, FTP 1900#, CK 20/64"</p>
	18:00 - 18:00	0.00	PROD	50				
3/18/2011	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2550#, TP 2150#, 20/64" CK, 48 BWPH, HVY SAND, - GAS TTL BBLS RECOVERED: 2228 BBLS LEFT TO RECOVER: 7763</p>
3/19/2011	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 3250#, TP 2100#, 20/64" CK, 39 BWPH, MED SAND, - GAS TTL BBLS RECOVERED: 3242 BBLS LEFT TO RECOVER: 6749</p>

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 920-12F			Spud Conductor: 11/9/2009			Spud Date: 11/10/2009		
Project: UTAH-UINTAH			Site: NBU 920-12F				Rig Name No: SWABBCO 1/1	
Event: COMPLETION			Start Date: 3/7/2011				End Date: 3/17/2011	
Active Datum: RKB @4,722.00ft (above Mean Sea Level)			UWI: SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/0/1,922.00/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
3/20/2011	7:00 -			33	A			7 AM FLBK REPORT: CP 3150#, TP 2000#, 20/64" CK, 32 BWPH, MED SAND, - GAS TTL BBLS RECOVERED: 4075 BBLS LEFT TO RECOVER: 5916
3/21/2011	7:00 -			33	A			7 AM FLBK REPORT: CP 2800#, TP 1800#, 20/64" CK, 25 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 4734 BBLS LEFT TO RECOVER: 5257
3/24/2011	7:00 -			50				WELL IP'D ON 3/24/11 - 1900 MCFD, 0 BOPD, 440 BWPD, CP 2280#, FTP 1498#, CK 20/64", LP 131#, 24 HRS

## 1 General

### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

### 1.2 Well Information

Well	NBU 920-12F	Wellbore No.	OH
Well Name	NBU 920-12F	Common Name	NBU 920-12F
Project	UTAH-UINTAH	Site	NBU 920-12F
Vertical Section Azimuth	156.18 (°)	North Reference	True
Origin N/S	0.0 (ft)	Origin E/W	0.0 (ft)
Spud Date	11/10/2009	UWI	SE/NW/0/9/S/20/E/12/0/0/26/PM/N/1,957.00/W/ 0/1,922.00/0/0
Active Datum	RKB @4,722.00ft (above Mean Sea Level)		

## 2 Survey Name

### 2.1 Survey Name: Survey #1

Survey Name	Survey #1	Company	PROPETRO
Started	11/10/2009	Ended	
Tool Name	INC	Engineer	Anadarko

#### 2.1.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
14.00	0.00	0.00	14.00	0.00	0.00

#### 2.1.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
11/10/2009	Tie On	14.00	0.00	0.00	14.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11/11/2009	NORMAL	1,824.00	1.00		1,823.91	15.79	0.00	-14.45	0.06	0.06	0.00	0.00
11/12/2009	NORMAL	2,724.00	1.50		2,723.69	35.43	0.00	-32.41	0.06	0.06	0.00	0.00

### 2.2 Survey Name: Survey #2

Survey Name	Survey #2	Company	SCIENTIFIC
Started	12/23/2010	Ended	
Tool Name	MWD	Engineer	JARED

#### 2.2.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
2,724.00	1.50	0.00	2,723.69	35.43	0.00



## 2.2.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
12/23/2010	Tie On	2,724.00	1.50	0.00	2,723.69	35.43	0.00	-32.41	0.00	0.00	0.00	0.00
12/24/2010	NORMAL	2,824.00	0.88	212.82	2,823.68	36.09	-0.42	-33.18	2.29	-0.62	-147.18	-167.97
	NORMAL	3,395.00	1.32	173.26	3,394.58	25.88	-2.02	-24.49	0.15	0.08	-6.93	-80.70
	NORMAL	3,899.00	0.70	157.00	3,898.50	17.28	-0.14	-15.86	0.13	-0.12	-3.23	-163.17
12/25/2010	NORMAL	4,403.00	1.14	211.15	4,402.44	10.15	-1.53	-9.90	0.18	0.09	10.74	92.00
	NORMAL	4,911.00	0.53	164.91	4,910.39	3.56	-3.53	-4.68	0.17	-0.12	-9.10	-153.67
	NORMAL	5,418.00	1.49	180.12	5,417.31	-5.30	-2.93	3.66	0.19	0.19	3.00	23.30
	NORMAL	5,923.00	0.44	154.72	5,922.23	-13.62	-2.12	11.60	0.22	-0.21	-5.03	-170.20
	NORMAL	6,428.00	1.06	178.19	6,427.19	-20.04	-1.14	17.87	0.13	0.12	4.65	38.42
12/26/2010	NORMAL	6,936.00	1.14	167.29	6,935.09	-29.67	0.12	27.19	0.04	0.02	-2.15	-74.58
	NORMAL	7,442.00	1.93	168.17	7,440.91	-42.92	2.97	40.46	0.16	0.16	0.17	2.15
12/27/2010	NORMAL	7,912.00	1.73	150.97	7,910.67	-56.87	8.04	55.27	0.12	-0.04	-3.66	-118.46
12/28/2010	NORMAL	8,421.00	1.76	147.25	8,419.44	-70.16	15.99	70.64	0.02	0.01	-0.73	-77.03
	NORMAL	8,798.00	1.75	134.24	8,796.26	-79.04	23.25	81.70	0.11	0.00	-3.45	-97.93
12/30/2010	NORMAL	9,275.00	1.93	149.94	9,273.02	-91.08	32.49	96.44	0.11	0.04	3.29	78.31
12/31/2010	NORMAL	9,749.00	1.76	147.86	9,746.77	-104.15	40.36	111.58	0.04	-0.04	-0.44	-159.54
1/1/2011	NORMAL	10,216.00	1.93	148.57	10,213.53	-116.93	48.28	126.47	0.04	0.04	0.15	8.01
1/6/2011	NORMAL	10,904.00	1.93	148.57	10,901.14	-136.70	60.36	149.43	0.00	0.00	0.00	0.00